

# Eesti

Töö 1: Ühel katuseosal tuleb eemaldada kolm vana, kasutusest väljas antennimasti, parandada nende all olev hüdroisolatsioonikiht ja paigata plekk-katus veepidavaks.

Töö 2: Teisel katuseosal tuleb demonteerida katust läbiv teraskorstna toru, parandada hüdroisolatsioon ja paigata katus. Toru eemaldamisel jääb ava ka soojustusse, aurutõkkesse, kipslakke ja vahelakke - need tuleks seestpoolt sulgeda: soojustus taastada, aurutõke paigata, kipslagi ja vahelae ava kinni ehitada.

# English

Job 1: On one roof section, three old, unused antenna poles need to be removed, the waterproofing layer underneath repaired, and the metal roof patched watertight.

Job 2: On another roof section, a steel chimney pipe passing through the roof needs to be removed, the waterproofing repaired, and the roof patched. Removing the pipe leaves an opening through the insulation, vapor barrier, drywall ceiling and mid-floor - these should be closed from inside: insulation re-filled, vapor barrier patched, drywall ceiling and mid-floor opening rebuilt.